333

SHIMOGA DIVISION.

ADVERTISEMENT.

The 11th August 1887.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 21st August 1887, for constructing a bridge of 3 spans, 20 feet each over Umachihalla, on Sagar-Siralkoppa road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes as earnest money and be superscribed "Tender for constructing a bridge over Umachihalla," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of Work.	Per.	Quantity.	Rate.	Remarks.
Excavation cutting bank	C. yd.	929		
Do foundation	Do	152		
Do do	Do	305		
Baling water	Lumpsum.			
Brick in Surkee mortar foundation	C. feet.	9,827		
Do ordinary mortar superstructure ..	Do	13,514		
Archwork	Do	1,915		
Plastering with mortar	Sq.	66·39		
Cornice work	R. feet.	246		
Centrings	Each.	3		
Guard stones	Do	8		
Earth filling.	C. yd.	3,018		
Turfing	Sqr.	154·57		
Gravelling	C. yd.	178		
Rough stone work	Do	336		

A. S. NAGAVKAR,
Executive Engineer.